

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-19018-00-00  
Spot: SESESENW - Sec/Twnshp/Rge: 21-31S-8W  
2726 feet from S Section Line, 2678 feet from E Section Line  
Lease Name: BURGESS SWDW Well #: 3-21  
County: HARPER Total Vertical Depth: 4484 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4416		250 SX
SURF	8.625	250		225 SX

Well Type: SWD UIC Docket No: D11225.0 Date/Time to Plug: 07/25/2012 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE OLIVER Company: Phone:

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/30/2012 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

3869' OF 2 7/8 TUBING CEMENTED INSIDE 4.5 CASING. RAN IN WITH 1 1/4" TUBING TO 3820', PUMPED 15 SXS OF GEL AND 25 SXS OF CEMENT ON 8/29/12 LET SIT OVERNIGHT. TAGGED BOTTOM PLUG AT 3200' WITH TUBING, CIRCULATE TO SURFACE WITH 80 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3896	3952		

RECEIVED  
SEP 12 2012  
KCC WICHITA

Remarks: QUALITY WELL SERVICE, PROVIDED CEMENT ALSO. WELL WOULD NOT PASS MIT.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

cc to MIC 9/14/12  
9/20/12

1/2