

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21162-00-00
Spot: NESE Sec/Twnshp/Rge: 15-25S-9W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: ARCHIE B Well #: 1-15
County: RENO Total Vertical Depth: 4000 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3999	1751	160 SX
SURF	8.625	179		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2012 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (620) 234-5191

Proposed Plugging Method: According to the rules and Regulations of the KCC

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/24/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3785' - CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING OFF @ 1751' PULLED CASING TO 1466' SPOTTED 35 SXS CEMENT. PULLED CASING TO 811' SPOTTED 35 SXS CEMENT. PULLED CASING TO 251' CIRCULATED TO SURFACE WITH 130 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3830	3840		MISSISSIPPIAN

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40/4% POS MIX, TICKET #39997

Plugged through: CSG

District: 02

Signed

B. J. HOPE
✓ 9/20/12

(TECHNICIAN)