

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21350-00-00
Spot: E2E2SW Sec/Twnshp/Rge: 15-33S-6W
1320 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CAROTHERS E Well #: 1
County: HARPER Total Vertical Depth: 4590 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4589		100 SX
SURF	8.625	257		175 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/25/2012 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/25/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

4382' - SET CIBP CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3214' PULLED CASING. RAN TUBING INTO 1091' SPOTTED 50 SX CEMENT. WAITED 1.5 HOURS TAGGED PLUG @ 850, PULLED TUBING TO 717' SPOTTED 35 SX CEMENT. PULLED TUBING TO 312' CIRCULATED TO SURFACE WITH 85 SX CEMENT. CHECK TOP PLUG ON 7/26/12 SURFACE PIPE FULL.

Perfs:

Top	Bot	Thru	Comments
4430	4450		

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: ALLIED OUT OF MEDICINE LODGE, 60/40/4% POS MIX, TICKET #

Plugged through: TBG

District: 02

Signed B. J. Hope
9/20/12 (TECHNICIAN)