

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10211-00-01
Spot: SWNWNW Sec/Twnshp/Rge: 7-27S-12W
4310 feet from S Section Line, 4815 feet from E Section Line
Lease Name: ICHU Well #: 12
County: PRATT Total Vertical Depth: 4285 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4254	0	WITH 125 SX CMT
SURF	8.625	403		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2012 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SAND BACK 50' ABOVE OPEN HOLE. PERFORATE @ 680'. PUMP DOWN 5 1/2" CASING WITH CMT FILLING 5 1/2" CASING & CIRCULATING CMT TO SURFACE IN 5 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2012 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SANDED BACK TO 4037' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PERFORATE @ 680'. PUMPED DOWN 5 1/2" CASING WITH 350 SX CMT. BROKE CIRCULATION INITIALLY. LOST RETURNS EARLY ON. REESTABLISHED BLOW BUT NO RETURNS THROUGHOUT REST OF JOB. WAS PUMPING SLOW RATE TO KEEP PRESSURE DOWN. SHUT DOWN TO LET CMT SET. 8/30/12: CUT BRADEN HEAD OPEN. CHECK TOC ON 5 1/2" X 8 5/8" & FOUND AT 114'. TOC INSIDE 5 1/2" CASING @ 30'. 9/6/12: TOP OFF 5 1/2" CASING WITH 5 SX CMT & 5 1/2" X 8 5/8" ANNULUS WITH 68 SX CMT.


RECEIVED
SEP 13 2012
KCC WICHITA

Remarks: COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

SEP 11 2012

KCC DODGE CITY

RAW