

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-107-24601-00-00
Spot: SWSESW Sec/Twnshp/Rge: 35-21S-22E
428 feet from S Section Line, 3827 feet from E Section Line
Lease Name: LANHAM (361) 352122 Well #: C5
County: LINN Total Vertical Depth: 820 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	21		8 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/27/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JIM STEGEMAN Company: COLT ENERGY Phone: (620) 365-3100

Proposed Plugging Method: 200' plug at TD (820'), 50' plug at 500', 250' to surface. The btm plug is longer than normal in order to plug off a zone that is producing in nearby well.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 04/27/2012 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

CONSOLIDATED HOOKED TO 2-INCH TUBING AND BROKE CIRCULATION W/ FRESH WATER THEN CLEANED & CONDITIONED WELL WITH 200# GEL FLUSH. PUMPED 58 SACKS OF CEMENT AT 820 FEET THEN PULLED TUBING UP TO 450' PUMPED 200# GEL FLUSH, THEN PUMPED 15SXS CEMENT. PULLED 2-INCH TUBING UP TO 250' PUMPED 78 SACKS OF CEMENT FROM 250' TO SURFACE. PULLED TUBING OUT OF HOLE THEN TOPPED WELL OFF. TOTAL CEMENT USED 138SXS.

Perfs:

RECEIVED
SEP 11 2012
KCC Chanute Dist. #3
LS

RECEIVED
SEP 13 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed L. Short
9/19/12 (TECHNICIAN)