

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00234-00-01  
Spot: SWSWSWSW Sec/Twnshp/Rge: 7-5S-21W  
299 feet from S Section Line, 5070 feet from E Section Line  
Lease Name: NOONE Well #: 1  
County: NORTON Total Vertical Depth: 1400 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1398		350 SX
SURF	8	234		140 SX

Well Type: SWD UIC Docket No: D21381.0 Date/Time to Plug: 09/05/2012 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 125 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Inj. Perforations: 1212'-1242'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/05/2012 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing. Pumped 100 sx cement w/400 # hulls. Casing went on vacuum.  
Stopped pumping.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 25 sx cement. Maximum pressure 125 psi.  
Topped off 4 1/2" casing with 35 sx cement.

Perfs:

Top	Bot	Thru	Comments
1212	1242		

RECEIVED  
SEP 14 2012  
KCC WICHITA

Remarks: SWIFT SERVICES TICKET # 21945

Plugged through: CSG

District: 04

Signed Pat Bedore  
9/19/12 (TECHNICIAN)  
cc to UIC 9/14/12

CM

SEP 11 2012