

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20226-00-00
Spot: NESESWSW Sec/Twnshp/Rge: 7-5S-21W
507 feet from S Section Line, 4161 feet from E Section Line
Lease Name: NOONE Well #: 7
County: NORTON Total Vertical Depth: 3500 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3499		160 SX
SURF	8.625	210		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2012 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2012 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 2000'. Pumped 100 sx cement w/300 # hulls.
Pulled tubing to 1000'. Pumped 100 sx cement w/100 # hulls to circulate cement to the surface.
Pulled all tubing, hooked to 4 1/2" casing and pumped 40 sx cement. Maximum pressure 750 psi. Shut in pressure 500 psi.
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 35 sx cement. Maximum pressure 125 psi.

RECEIVED
SEP 14 2012
KCC WICHITA

Remarks: SWIFT SERVICES TICKET # 21944

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

9/19/12

SEP 11 2012