

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00466-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 28-19S-12W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: JOHNSON AB Well #: 1
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2904		
CIBP		3250		
CIBP		3316		
PROD	5.5	3381		110 SX
SURF	8.625	163		163 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2012 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL INC. Phone: (620) 562-8088

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.
Perforations already sanded off T/A well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 630' and 190'.
Ran tubing to 3000'. Pumped 14 sx gel.
Pulled tubing to 1450'. Circulated cement to surface on casing w/160 sx cement.
Pulled tubing. Tied to casing and pumped 8 sx cement. Pressured to 600 psi.
Tied to surface pipe and pumped 5 sx cement.

Perfs:

Top	Bot	Thru	Comments
3195	3199		
2917	2921		

RECEIVED
SEP 14 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

✓ 9/20/12

CM

SEP 11 2012