

1 080314

Handwritten mark

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,697-00-00

SW SW NE, SEC. 3, T 34 S, R 29 ^(W)

2790 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Hissom Well # 1

Operator: TXO Production Corp.

County Meade 175.50

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5400 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1424 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 22 Month: January Year: 19 85

Plugging proposal received from Tom Harmon

(company name) H-30 (phone) 316-263-2043

work: to fill hole with heavy mud and spot cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1985
CONSERVATION DIVISION
Wichita, Kansas

1st plug at 1470' with 50 sx cement

2nd plug at 700' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 9:00 pm Day: 22 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 700' with

50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE 1-31-85

INV. NO. 6789

Signed J. H. Metz
(TECHNICIAN)

1-22