

To: 1 080086  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202 ✓ 11-18  
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 071-20,644 - 0000  
SW SW , SEC. 12 , T 17 S, R 41 W/E  
660 feet from S section line  
4620 feet from E section line

Operator License # 30606  
Operator: Murfin Drilling Co., Inc.  
Name & Address: 250 N. Water, Ste. 300  
Wichita, KS 67202

Lease Name Sandifer Well # 1  
County Greeley 104.13  
Well Total Depth 3204 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 11 a.m. Day: 18 Month: 11 Year: 19 96

Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 3204' w/125 sx cement, PBSD 3158', Perfs at 2950-53, 2959-62'

1st plug sand back to 2900' and dump 4 sx cement on top of sand through bailer,

2nd plug at 1750' with 80 sx cement,

3rd plug at 900' with 50 sx cement,

4th plug at 360-390' with 50 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 18 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 2900' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 80 sx cement at 1750';

3rd plug pulled to 900' and pumped 50 sx cement,

4th plug pulled to 360' and pumped 50 sx cement,

5th plug pulled to 40' and pumped 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1750' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (date) observe this plugging.

DATE 11-22-96

INV. NO. 47034

Signed Kevin D. Shab (TECHNICIAN)

RECEIVED  
MANSAS CORP  
NOV 21 P 18  
11-21-96