

1 030951

5-23-88

439
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,454-0000
130' S of C NW SW NW, SEC. 32, T 17 S, R 41 W/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 3504

3500 feet from S section line
4950 feet from E section line

Lease Name Harris Well # 1

Operator: Spurlock & Spines Exploration, Inc.
Name & Address: 525 Fourth Financial Center
Wichita, KS 67202

County Greeley 179.34

Well Total Depth 5518 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 598

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 23 Month: 5 Year: 19 88

Plugging proposal received from John Schlenz

(company name) H-30 Drilling, Inc. (phone) 316-263-2043

Elevation 3727'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2475'

1st plug at 2460' with 80 sx cement, 2nd plug at 1560' with 50 sx cement;

3rd plug at 630' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 23 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2460' with 80 sx cement,

2nd plug at 1560' with 50 sx cement,

3rd plug at 630' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 7 1988

6-7-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED / did not observe this plugging.

DATE 6-23-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 20944

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: May 10 1988

OPERATOR: License # 3504
Name: Spurlock & Spines Exploration, Inc.
Address: 525 South Financial Center
City/State/Zip: Wichita, KS 67202
Contact Person: Robert C. Spurlock
Phone: 316/264-2808

CONTRACTOR: License # 5107
Name: H-30 Drilling, Inc.
City/State: Wichita, KS 67202

Well Drilled For: X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
Date: 5/2/88 Signature of Operator or Agent: Robert C. Spurlock Title: President

For KCC Use:
Conductor Pipe Required: 200 feet per Alt.
This Authorization Expires: 11-3-88 Approved By: RCH 6-3-88

EFFECTIVE DATE: 5-8-88

Speed 5/17/88 10:00PM
598' 8 5/8" (HW)
Allied Site Care

API Number 15-071-20,454-0000
130' South of Center
NW SW NW Sec. 32 Twp. 17 S. Rg. 41W
3500 Ft. from South Line of Section
4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line: 330 feet
County: Greeley
Lease Name: HARRIS Well # 1
Ground surface elevation: 2727 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 1700'
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set: 600'
Conductor pipe required
Projected Total Depth: 5400' feet
Formation: Mississippian

130' South of Center
NW SW NW Sec. 32 Twp. 17 S. Rg. 41W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Length (ft.). Includes rows for 1st through 5th plugs and bathole/mousehole to surface minus 5 feet.

Vertical log entries:
PUSHER: Joh Schlenz
TD: 5518 FORMATION MISS-
SURFACE PIPE: 8 5/8" @ 598'
ANHYDRITE: 2475 ELEVATION 3727
STARTING TIME & DATE: 5-23-88 1:00 AM
COMPLETION TIME & DATE: 5-23-88 4:30 AM
1st PLUG @ 2460 FT. W/ 80 SX
2nd PLUG @ 1560 FT. W/ 80 SX
3rd PLUG @ 630 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ Hand
CEMENT COMPANY: 4/4 P02 6010
TECHNICIAN: SA

RECEIVED
STATE CORPORATION COMMISSION

JUN - 7 1988

CONSERVATION DIVISION
Wichita, Kansas