

1 050818

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,271-0000

NW NW NE , SEC.31 , T 17 S, R 41 W
4620 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153
Operator: Texaco, Inc.
Name & Address: P. O. Box 2420
Tulsa, OK 74102

Lease Name Greeley Land Well # 1
County Greeley 190.13
Well Total Depth 5850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 608

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P. O. Box 501, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 26 Month: March Year: 19 86

Plugging proposal received from Richard Wilkinson

(company name) Texaco (phone) 316-624-0131

were: 5 1/2" at 5850' Perfs at 2942-2946' DV at 4392' CIBP at 3310'

- 1st plug pump 1 sack hulls and 20 sx cement to bottom and push plug to 2900'
- 2nd plug on stub with 40 sx cement
- 3rd plug at 650' with 50 sx cement
- 4th plug from 40' to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 26 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 20 sx cement to bottom and stopped plug at 2900', 2nd plug at 1400' with 50 sx cement, 3rd plug at 650' with 50 sx cement, 4th plug from 40' to surface with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION JUN 16 1986 6-16-86

Remarks: Recovered 1417' 5 1/2" casing. Used Class H cement by Sargent's (if additional description is necessary, use BACK of this form.)

Inspector (if not) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE JUN 18 1986

INV. No. 14155 JUN 26 1986