

To: 1 080143 9-10
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-071-20,078-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 4894

Operator: Horseshoe Operating, Inc.

Name & Address: 500 W. Texas, Ste. 1190
Midland, TX 79701

C NW NW, SEC. 26, T 20 S, R 40 W/8

4620 feet from S section line

4620 feet from E section line

Lease Name Coupland Well # 3

County Greeley 92.95

Well Total Depth 2860 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 10 Month: 9 Year: 19 97

Plugging proposal received from Skip Burns

(company name) Horseshoe Operating, Inc. (phone) 915-683-1448

were: 4 1/2" at 2860' w/200 sx cement, Perfs at 2827-35'

1st plug pump 25 sx cement with 100 lbs. hulls,

2nd plug perforate at 1350' and pump 80 sx cement, displace to 900',

3rd plug shoot casing, pump 50 sx cement at 640',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 10 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT On 6/2/97, Allied pumped 25 sx 60/40 Pozmix 6% gel cement with 100 lbs. hulls. Maximum pressure 300 psi. Shut in:

9/10/97 Peak Wireline Service found free point of casing at 800'. Perforated at 1350'.

2nd plug pumped 80 sx cement, displaced to 900'. Maximum pressure 1000 psi and shut in 450 psi.

Left shut in 60 minutes and released. Top of cement at 800'. Peak Wireline Service ran

in hole, shot 4 1/2" casing at 803'. 3rd plug pulled casing to 640', pumped 50 sx cement. (Over)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 803' of 4 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)
(old / ~~xxxxxx~~) observe this plugging.

DATE 9-16-97

INV. NO. 49014

9-10

Signed Kevin P. Strube
(TECHNICIAN)

ACTUAL PLUGGING REPORT CONTINUED:

4th plug pulled up to 40' and pumped 10 sx cement. Hole stayed loaded.

8

10/10/41
HAG
10/10/41