

1 050555

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,101-0000 *R*

C NW NW , SEC. 24 , T 20 S, R 40 W/EX

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9922

Lease Name Watson Well # 2

Operator: Hughes Seewald

County Greeley 94.19

Name & Address P. O. Box 1650

Well Total Depth 2898 feet

Amarillo, TX 79105

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 11:00 am Day: 11 Month: June Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 2898' PBD 2898' Perfs at 2810-20' Spot through 4 1/2" with mud between plugs

1st plug pump 25 sx hulls and 25 sx cement to bottom

2nd plug at 1200' with 50 sx cement 3rd plug at 600' with 40 sx cement

solid bridge

4th plug at 260' with 40 sx cement 5th plug hulls - plug at 40' -- cement to

surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:00 pm Day: 13 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx hulls and 25 sx cmeent to bottom, 2nd plug

at 1200' with 50 sx cement, 3rd plug at 600' with 40 sx cement, 4th plug at 260' with

40 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1985

6-17-85

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used Common Cement by Midwest casing pulling. Recovered 2045' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Clyde Wiley observed part of the plugging  
(did not observe) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 6-20-85

INV. NO. 8636