

1 070816

6-8

API NUMBER 15-071-20,013-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NE, SEC. 22, T 20 S, R 40 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9922

Lease Name Wallace Well # 1

Operator: Hughes Seewald  
Name &

County Greeley 92.11

Address P.O. Box 2587  
Liberal, KS 67905-2587

Well Total Depth 2834 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pullers License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 7 Month: 6 Year: 19 90

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pullers (phone) 316-675-8349

were: 4 1/2" at 2833' w/125 sx cement, PBD 2825', Perfs at 2809-15', Squeezed at 1139'

1st plug pump 2 sx hulls and 20 sx cement.

Spot plug through casing:

2nd plug at 1300' with 80 sx cement, 3rd plug at 650' with 40 sx cement,

4th plug at 430' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 8 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx common cement to perfs,  
pressured to 700# and held.

Spotted plugs through casing:

2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 40 sx cement,

4th plug at 430' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Remarks: Used common cement by Midwest Casing Pullers. Recovered 1380' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 6-25-90

INV. NO. 28464

STATE OF KANSAS  
JUN 13 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dan Johnson  
(TECHNICIAN)