

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23809-00-00  
Spot: SESESWNW Sec/Twnshp/Rge: 20-15S-15W  
2500 feet from N Section Line, 1050 feet from W Section Line  
Lease Name: LAYHER TRUST ET AL Well #: 1-20  
County: RUSSELL Total Vertical Depth: 3440 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	733		400 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2012 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 185 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE  
Date/Time Plugging Completed: 07/17/2012 6:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st plug @3320 w/25 sx  
2nd plug @920 w/25 sx  
3rd plug @350 w/80 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 04 2012  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Darrel Dipman  
9/10/12 (TECHNICIAN)

OM

AUG 15 2012