

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21269-00-00
Spot: NENENE Sec/Twnshp/Rge: 2-16S-9W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: KATZENMEIER A Well #: 1-2
County: ELLSWORTH Total Vertical Depth: 3215 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	278		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/25/2011 6:30 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: _____ Company: ROYAL DRILLING Phone: _____

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 10/25/2011 9:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

PUMP 35 SX'S @ 3146', PULL DP TO 1050' & PUMP 35 SX'S, PULL DP TO 750' & PUMP 35 SX'S, PULL DP TO 329' & PUMP 35 SX'S, PULL DP TO 60' & CIRCULATE 25 SX'S TO SURFACE. 20 SX'S IN RAT HOLE. 15 SX'S IN MOUSE HOLE.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. USED 200 SX'S.

Plugged through: DP

District: 02

Signed Virgil Clothier
9/10/12 (TECHNICIAN)