

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22663-00-00
Spot: SESENE Sec/Twnshp/Rge: 5-19S-10W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: HADDON Well #: 3-5
County: RICE Total Vertical Depth: 3440 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	390		180 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/28/2011 4:30 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: KURT STRUBE Company: DISCOVERY DRILLING Phone: (620) 793-2046

Proposed Plugging Method: AS DIRECTED BY KCC, VIRGIL CLOTHIER

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 10/28/2011 6:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

PUMP 35 SX'S THRU DP @ 3333', PULL DP TO 1250' & PUMP 35 SX'S, PULL DP TO 900' & PUMP 35 SX'S, PULL DP TO 440' & PUMP 35 SX'S, PULL DP TO 60' & CIRCULATE CEMENT TO SURFACE. 15 SX'S IN RAT HOLE. 10 SX'S IN MOUSE HOLE.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. USED 190 SX'S.

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓ 9/10/12