

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20244-00-00
Spot: SWNE Sec/Twnshp/Rge: 15-22S-42W
3339 feet from S Section Line, 1998 feet from E Section Line
Lease Name: CHEATUM Well #: 4-15
County: HAMILTON Total Vertical Depth: 2748 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2736	0	WITH 550 SX CMT
SURF	8.625	353		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2012 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS VIA CASING. DISPLACE WITH WATER TO SHUT OFF. RUN BOND LOG TO DETERMINE TOC. PERFORATE USABLE WATER IF REQUIRED. CIRCULATE CMT TO SURFACE. IF 4 1/2" IS CEMENTED TO SURFACE, WILL NOT NEED TO PERFORATE. RUN TBG TO 1250' +/- & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2012 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT WITH 150# HULLS TO 2618'. RAN BOND LOG FROM 1430' TO 50'. STACKED OUT @ 1443'. TOC BEHIND 4 1/2" CASING IS 875'. PERFORATE AT 820'. RUN TBG TO 1392'. SPOT 30 SX CMT WITH 50# HULLS TO FILL FROM 1392' TO 900'. FULL RETURNS. PULL TBG TO 819'. CIRCULATE 4 1/2" CASING & 4 1/2" X 7 7/8" ANNULUS FULL OF CMT TO SURFACE WITH 155 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2608	2618		WINDFIELD

RECEIVED
SEP 06 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
SEP - 4 2012
KCC DODGE CITY

Handwritten initials