

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10291-00-02

Spot: SENW

Sec/Twnshp/Rge: 7-35S-41W

3298 feet from S Section Line, 3314 feet from E Section Line

Lease Name: MCCLUNG A

Well #: 1

County: MORTON

Total Vertical Depth: 5412 feet

Operator License No.: 5447

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2852		WITH 2 SX CMT
CIBP		3315		
PROD	4.5	3489	0	WITH 300 SX CMT
SURF	8.625	1506		WITH 700 SX CMT
UNK		3050		plug off zone- 400 sx cement
UNK		3430		CMT RETAINER

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/21/2012 12:30 PM

Plug Co. License No.: 32833

Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.

Proposal Rcvd. from: JOHN SCHOOLCRAFT

Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/22/2012 12:30 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2852' WITH 2 SX CMT. TOC FROM PRIMARY JOB IS 2280'. SQUEEZED AT 1358' TO 973' WITH 200 SX CMT. 4 1/2" CEMENTED FROM 1580' TO 0' PER BOND LOG. 1ST PLUG AT 1550' WITH 25 SX CMT. 2ND PLUG AT 600' TO 0' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3440	3452		
3406	3418		
3282	3290		
3252	3260		
3209	3222		
3189	3195		
3178	3184		
3158	3167		
2952	2960		
2919	2925		
2904	2914		
2887	2893		
0			

RECEIVED

SEP 06 2012

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

RECEIVED

AUG 28 2012

KCC DODGE CITY

Signed

(TECHNICIAN)

RAW7