

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-073-23945-00-00  
Spot: NENE Sec/Twnshp/Rge: 10-26S-9E  
660 feet from N Section Line, 660 feet from E Section Line  
Lease Name: HUNTINGTON Well #: 10-41  
County: GREENWOOD Total Vertical Depth: 2388 feet

Operator License No.: 31772  
Op Name: BLACK STAR 231 CORP.  
Address: LIVESTOCK EXCHANGE BLDG 1600  
KANSAS CITY, MO 64102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2388	150	150 SX
SURF	8.625	207	103	103 SX

Well Type: CM UIC Docket No: Date/Time to Plug: 08/09/2012 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BLACK STAR 231 CORP Company: Phone: (816) 560-7300

Proposed Plugging Method: Shot casing at about 800 feet from surface, draw casing. Set 50' plug at TD, 50' plug at top of casing, and 250' plug from 250' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 08/09/2012 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

RAN TUBING TO 2345' PUMPED 15 SXS CEMENT, PULLRD TUBING OUT, SHOT CASING @ 800' PUMPED 30 SXS CEMENT, PULLED CASING OUT, RAN TUBING TO 260' PUMPED 86 SXS CEMENT TO SURFACE, GEL SPACERS BETWEEN CEMENT PLUGS.

RECEIVED

SEP 4 2012

KCC Chanute Dist. #3

MH

RECEIVED  
SEP 06 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Mike D. [Signature]  
(TECHNICIAN)