

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-23946-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 35-27S-9E
1982 feet from N Section Line, 692 feet from E Section Line
Lease Name: SCHOENHALF Well #: 35-42
County: GREENWOOD Total Vertical Depth: 2498 feet

Operator License No.: 31772
Op Name: BLACK STAR 231 CORP.
Address: LIVESTOCK EXCHANGE BLDG 1600
KANSAS CITY, MO 64102

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP | | 2336 | | |
| PROD | 5.5 | 2498 | 695 | 120 SX |
| SURF | 6.125 | 205 | | 93 SX |

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 08/13/2012 11:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JIM PRYOR Company: _____ Phone: (816) 560-7300

Proposed Plugging Method: Draw casing above cement. 50' cement plug at PBSD (2336) 50' plug at top of casing. 250' plug from 250' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed 08/13/2012 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

RAN TUBING TO 2306' PUMPED 15 SXS CEMENT, PULLED TUBING TO 2016'
PUMPED 15 SXS CEMENT, PULLED TUBING OUT ,SHOT CASING @ 695' PUMPED 30
SXS CEMENT, PULLED CAASING OUT, RAN TUBING TO260' PUMPED 82 SXS
CEMENT TO SURFACE,GEL SPACERS BETWEEN CEMENT PLUGS.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2340 | 2343 | | |
| 2319 | 2321 | | |
| 2183 | 2185 | | |
| 2157 | 2159 | | |
| 2127 | 2129 | | |
| 2061 | 2063 | | |

RECEIVED

SEP 4 2012 MH

KCC Chanute Dist. #3

RECEIVED

SEP 06 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Duff
(TECHNICIAN)