

1080070

6-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,515-0000

SW SE NW, SEC. 11, T 18 S, R 43 W/E

3150 feet from S section line

3890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Brewer Well # 3

Operator: Amoco Production Company

County Greeley 172.25

Name & Address

P.O. Box 800, Rm. 1833

Well Total Depth 5300 feet

Denver, CO 80201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 532

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Exeter Drilling License Number 3098

Address

Company to plug at: Hour: 9:38 a.m. Day: 22 Month: 6 Year: 19 90

Plugging proposal received from Dan Bell

(company name) Amoco Production Company (phone) 303-830-4009

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2600'

1st plug at 2600' with 50 sx cement, 2nd plug at 1600' with 50 sx cement,

3rd plug at 750' with 80 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Tom Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:35 p.m. Day: 22 Month: 6

ACTUAL PLUGGING REPORT 1st plug at 2600' with 50 sx cement,

RECEIVED STATE CORPORATION COMMISSION

2nd plug at 1600' with 50 sx cement,

JUN 27 1990 6-27-90

3rd plug at 750' with 80 sx cement,

CONSERVATION DIVISION Wichita, Kansas

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement,

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 7-3-90

Signed Mike Spain (TECHNICIAN)

INV. NO. 28532

SEP 14 1990

FORM CP-2/3 Rev. 01-84

6-22