

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21101-00-01  
Spot: NWSESWSE Sec/Twnshp/Rge: 32-31S-41W  
658 feet from S Section Line, 1686 feet from E Section Line  
Lease Name: HANKE OWWO Well #: 1-32  
County: MORTON Total Vertical Depth: 5426 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: PO BOX 559  
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5175		WITH 2 SX CMT
PROD	4.5	5378	2658	WITH 125 SX CMT
SURF	8.625	1508		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2012 1:00 PM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: CIBP @ 5175' WITH 2 SX CMT. PLUG AT 1550' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/20/2012 8:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5175' WITH 2 SX CMT. 1ST PLUG AT 1540' WITH 50 SX CMT. 2ND PLUG AT 594' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5378	5426		
5260	5264		
5237	5245		

RECEIVED  
SEP 06 2012  
KCC WICHITA

Remarks: USED CLASS A COMMON CEMENT BY ALLIED.

Plugged through: CSG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)  
9/20/12

RECEIVED  
AUG 28 2012  
KCC DODGE CITY

RAWZ