

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25433-00-00
Spot: NENESESE Sec/Twnshp/Rge: 21-17S-23W
1074 feet from S Section Line, 216 feet from E Section Line
Lease Name: FEHRENBACH UNIT Well #: 1-21
County: NESS Total Vertical Depth: 4540 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	235		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/23/2012 12:30 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1740' WITH 50 SX CMT. 2ND PLUG AT 960' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 08/23/2012 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1740' WITH 50 SX CMT. 2ND PLUG AT 960' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.


RECEIVED
SEP 10 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP - 5 2012

KCC DODGE CITY

✓ 9/20/12

R 11/28