

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21505-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 1-10S-20W
372 feet from S Section Line, 948 feet from E Section Line
Lease Name: SUTOR A Well #: 21
County: ROOKS Total Vertical Depth: 3780 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5 | 3779 | | 250 SX |
| SURF | 8.625 | 242 | | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2012 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO. INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered - 600 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Junk in well bore @ 3356'.
DV - 1675' w/800 sx cement.
Perforations: Lans 3494' - 3658' O.A.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2012 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Whitetail Crude ran in hole with tubing to 3300'. Consolidated rigged to tubing, mixed and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 2168'. Consolidated rigged to tubing and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1060'. Consolidated rigged to tubing and pumped 225 sx cement w/200 # hulls to circulate cement up 5 1/2" casing. Ran out of cement. Operator ordered an additional 100 sx cement.
Pulled tubing. Topped off 5 1/2" casing w/40 sx cement. Hole standing full.
Rigged to 8 5/8" casing. Pumped 20 sx cement to pressure w/300 psi. Shut in pressure 275 psi.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3648 | 3658 | | |
| 3625 | 3632 | | |
| 3610 | 3617 | | |
| 3550 | 3554 | | |
| 3536 | 3540 | | |
| 3511 | 3528 | | |
| 3494 | 3499 | | |

RECEIVED
SEP 10 2012
KCC WICHITA

Remarks: CONSOLIDATED CEMENTING CO TICKET # 37086

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

✓ 9/20/12

CM

AUG 31 2012