

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-20235-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 5-31S-9W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: JACOBS Well #: 1  
County: HARPER Total Vertical Depth: 4475 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4474		100 SX
SURF	8.625	216		175 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2012 12:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: SHANNON RAYBERN Company: \_\_\_\_\_ Phone: (620) 793-2672

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/18/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

PUMPED 75 SX CEMENT @ 4450'. PULLED TUBING, PERF. CASING AT 1550', 1100' & 266'. SPOTTED 75 SX CEMENT COMMON WITH 4% CC, @ 1550' WAITED 2 HOURS, COULD NOT TAG CEMENT. PUMPED 100 LBS HULLS, MIXED ANOTHER 150 LBS. HULLS WITH 75 SX CEMENT 3% CC. LET SET OVERNITE TAGGED UP AT 200', PUMPED 50 SX CEMENT DOWN BACKSIDE, 8 SX INSIDE 4.5. CHECKED TOP PLUG ON 7-20-12, WITH IN 2' TOP OF SURFACE CASING.

Perfs:

Top	Bot	Thru	Comments
4454	4460		

RECEIVED  
SEP 12 2012  
KCC WICHITA

Remarks: COPELAND OUT OF GREAT BEND, COMMON CEMENT, TICKET #39880.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*  
9/19/12

(TECHNICIAN)