

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20717-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 19-32S-5E
4684 feet from S Section Line, 4905 feet from E Section Line
Lease Name: PAYNE Well #: 3
County: COWLEY Total Vertical Depth: 2300 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L.
Address: PO BOX 381
WINFIELD, KS 67156

Handwritten: ALBERT L. COOPER
SERVING CO.

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2295		75 SX
SURF	8.625	150		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2012 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/23/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
4-23-2012, RIH ON WIRELINE SET PLUG @ 2255', SANDED BACK ON TOP OF PLUG @ 2135'. DUMP BAILED 5 SXS CEMENT ON TOP. 8-22-2012, RIH ON WIRELINE SHOT SQUEEZE HOLES 300'-301'. 8-23-2012, RIH W/TBG @ 300', COPELAND ACID SERVICE ESTABLISHED CIRCULATIOJN AND MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-23-2012. COPELAND ACID CEMENT TICKET #38060.

Perfs:

Top	Bot	Thru	Comments
2270	2275	CSG	

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: COMPLIANCE / 10 YR RULE/ DENIED TA
Plugged through: TBG

District: 02

Signed: *Duane Krueger*
(TECHNICIAN)
9/19/12