

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22154-00-00
Spot: SESW Sec/Twnshp/Rge: 28-33S-4E
660 feet from S Section Line, 2340 feet from W Section Line
Lease Name: RICHARDSON B Well #: 1
County: COWLEY Total Vertical Depth: 790 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L.
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	800		100 SXS CMT
SURF	7	200		100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/23/2012 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE COMPANY Phone: (316) 204-0072

Proposed Plugging Method: AS TO KCC RULES & REGS, PERF CASING @ 250', RUN TBG TO BOTTOM AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
PERFORATED SQUEEZE HOLES @ 250'-251'. ESTABLISHED CIRCULATION. RIH W/TBG @ 675', COPELAND ACID SERVICE MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TBG, SWEDGED INTO 4-1/2" CASING AND PUMPED ANOTHER 20 SXS. SIP @ 300#. CEMENT CIRCULATED. PLUG DOWN 8-23-2012 @ 5:00 PM. COPELAND ACID SERVICE CEMENT TICKET #38059.

Perfs:

Top	Bot	Thru	Comments
716	722	CSG	
680	688	CSG	

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: COMPLIANCE PLUGGING / TA
Plugged through: TBG

District: 02

Signed Duane Krueger
9/19/12 (TECHNICIAN)

JK