

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21442-00-00  
Spot: NENWNESE Sec/Twnshp/Rge: 19-23S-8W  
2313 feet from S Section Line, 743 feet from E Section Line  
Lease Name: MCGONIGLE Well #: 1  
County: RENO Total Vertical Depth: 3816 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3675		
PROD	4.5	3816		150 SX
SURF	8.625	275		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2012 4:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: JOE Company: GRESSEL OILFIELD SERVICE, LLC Phone: \_\_\_\_\_

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/23/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

3450' -SET CIBP CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2235' PULLED CASING. RAN TUBING TO 1326' SPOTTED 50 SX CEMENT WITH 5% CC. PULLED TUBING TO 799' SPOTTED 35 SX CEMENT WITH 5% CC. PULLED TUBING TO 334' CIRCULATED TO SURFACE WITH 155 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3708	3714		
3490	3496		

RECEIVED  
SEP 12 2012  
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET #38020.

Plugged through: TBG

District: 02

Signed B. J. Hope  
9/19/12 (TECHNICIAN)