

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21476-00-00
Spot: SEWNENE Sec/Twnshp/Rge: 4-34S-6W
2200 feet from S Section Line, 710 feet from E Section Line
Lease Name: METZ C Well #: 2
County: HARPER Total Vertical Depth: 4512 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4503		125 SX
SURF	8.625	312		250 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/19/2012 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/19/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

4452' - SET CIBP CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2903' PULLED CASING. RAN TUBING TO 1122' SPOTTED 35 SX CEMENT. WAITED 1.5 HOURS TAG CEMENT @ 790'. PULLED TUBING TO 717' SPOTTED 35 SX CEMENT. PULLED TUBING TO 374' CIRCULATED TO SURFACE WITH 125 SX CEMENT. CHECKED TOP PLUG ON 7/20/2012, CEMENT WITHIN 3' OF TOP OF SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
4503	4512		

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: ALLIED CEMENTING, 60/40/ 4% POS MIX, TICKET #54044

Plugged through: TBG

District: 02

Signed B. J. Hope
9/20/12 (TECHNICIAN)