

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21161-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 15-25S-9W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ARCHIE A Well #: 1-15  
County: RENO Total Vertical Depth: 4020 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4019		175 SXS CMT
PROD	5.5	4022		170 SX
SURF	8.625	183		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2012 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: \_\_\_\_\_

Proposed Plugging Method: According to the rules and Regulations of the KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/23/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3807'-CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1400', SPOTTED 35 SX CEMENT. PULLED CASING TO 789' SPOTTED 35 SX CEMENT. PULLED CASING TO 231' CIRCULATED TO SURFACE WITH 100 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3854	3868		MISSISSIPPIAN

RECEIVED  
SEP 12 2012  
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40/4% POS MIX, TICKET #39995

Plugged through: CSG

District: 02

Signed B. J. Hope  
9/20/12 (TECHNICIAN)