

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SW

Old hole opened up _____ SEC. 5 TWP. 11 RGE. 20

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Fisher~~ FischerOperator John Lindas Oil Co Address Wichita, KansField _____ County EllisTotal Depth 3751 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3751' with
100 sax cement behind - Lane Wells plugs to 3561' - top
perforations at 3346'.

Chat to 3320', set rock and 5 sax cement with dump bailer,
pulled 1550' 5 1/2" - filled with mud to 200', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1952

CONSERVATION DIVISION
Wichita, Kansas

Edwin Perry
District Conservation Agent

Date 12-18-52

PLUGGING

FILE SEC. 5-11-R 20W

BOOK 1427 62-1111-13