


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bldg., Wichita, Kansas

Lease Name Bittle "B" Well No. 1

Location C SE NW Sec. 33 Twp. 16 Rge. 20 (E) (W) XX

County Rush Total Depth 4016'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 8P Day 17 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4016' 8 5/8 csg set at 252' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messer
Well Plugging Supervisor

DATE 10/22/68
INV. NO. 8649-11