

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Inc.,

Complete Address: 410 4th Bat'l Bk, Bldg., Wichita, Kansas 67202

Lease Name Hunt Well No. 1

Location NW NE NW Sec. 34 Twp. 16 Rge. 20 (E) (W) X

County Rush Total Depth 3950'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12 N Day 27 Month 6 Year 1968

The Above well was plugged as follows:

Total Depth 3950' 8 5/8 csg set at 240' cwc.

5 1/2 csg set at 3949 cw 100 sc cement.

Filled 5 1/2 csg with sand to 3925 and dumped 5 sc cement with dump bailer.

Recov. 2685' of 5 1/2 csg.

Pumped thru 8 5/8 swage with 25 sc gel 1/6 hulls, Plug and 135 sc cement.

Max. pres. 500 lbs. SI pres. 200 lbs.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 1 1968

Signed:

Leo F. Messing
Well Plugging Supervisor

DATE 7/2/68

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 8020-4