

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John C. Graves Et al

Complete Address: 505 Union Center Wichita, Kansas

Lease Name Derr Well No. 1

Location SE SE SE Sec. 35 Twp. 16 Rge. 20 (E) (W) X

County Rush Total Depth 3950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 5:15P Day 30 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3950' 8 5/8 csg set at 221' cwc Cmt. Mat. 100 sc 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 10/2/68

INV. NO. 8563-W