

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-165-20,940-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Chief Drilling Co. Inc.

Complete Address 905 Century Plaza Wichita, KS

Lease Name Walker Well No. 1

Location NE-NE-NE Sec. 26 Twp. 16 Rge. 20 (East)(West)

County Rush Total Depth 3882

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Warrior Dr. Co. 905 Century Plaza

Address Wichita, KS License No. _____

Operation Completed: Hour: 10:00 AM Day: 5 Month: 11 Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

- 8 5/8" S.P. to 285' w/ 200 sx common 3% gel - 2% cc.
- Order 150 sx 50/50 Poemix 4% gel - 3% cc. & plug
- 1st plug @ 720' w/ 70 sx
- 2nd plug @ 270' w/ 40 sx
- 3rd Solite Bridge
- 4th Hells plug @ 40' -> cut to 0' w/ 10 sx
- 5th Rat hole w/ 5 sx w/ drill pipe
- 6th Mouse hole w/ 5 sx w/ drill pipe

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1981

CONSERVATION DIVISION
Wichita, Kansas
Can be replaced

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Dement
Conservation Division Agent

INVOICED
DATE 12-9-81
INV. NO. 8585-W