

15-165-20385-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
RECEIVED
APR 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Inc.
Complete Address 370 W. Wichita Avenue, Russell, Kansas
Lease Name Ryan Well No. 1
Location SW NE NE Sec. 27 Twp. 16 Rge. (E) (W) 20
County Rush Total Depth 3925'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 3:30 A Day 14 Month 4 Year 1971

The above well was plugged as follows:

RTD 3925' 8 5/8 csg set at 220' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 4/20/71

INV. NO. 3573-W