

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling CompanyComplete Address: 705 4th Nat'l Bk. Bldg., Wichita, KansasLease Name Bisagno "A" Well No. 1Location SE NE SE Sec. 16 Twp. 16 Rge. 20 (E) (W) XCounty Rush Total Depth 3984'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: \_\_\_\_\_ Co. Tools \_\_\_\_\_

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 1:30P Day 28 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3984' 8 5/8 csg set at 243' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
Signed: \_\_\_\_\_

OCT 1 - 1968

CONSERVATION DIVISION  
Wichita, Kansas

Well Plugging Supervisor Geo. F. Massey

INVOICED

DATE 10/1/68INV. NO. 8553-W