

KANSAS

*10*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas 67202

Lease Name Jennings "B" Well No. 1

Location C SW NE Sec. 17 Twp. 16 Rge. (E) (W) 20

County Rush Total Depth 4100'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools by HOWCO

Address      License No.     

Operation Completed: Hour 10:30 A Day 6 Month 3 Year 1972

The above well was plugged as follows:

RTD: 4100' 8 5/8 csg set at 276' cwc 150 sk Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 680' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo F. Murray*  
Well Plugging Supervisor

INVOICED

DATE 3-10-72

INV. NO. 5323-62