

15-165-20053-0000

9

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION

SEP 1 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bk. Bldg. Wichita, Kansas

Lease Name Moran "A" Well No. 1

Location SW SE SW Sec. 10 Twp. 16 Rge. 20 (E) (W) X

County Rush Total Depth 3992

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 9:45 A Day 31 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3992' 8 5/8 csg set at 237' cwc 175 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru drill

pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of

cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ F. Massey
Well Plugging Supervisor

DATE 9-1-67

INV. NO. 6241-W