

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 1425 Wichita Plaza Wichita, Kansas 67202

Lease Name Grumbein Well No. 1

Location SE SE NW Sec. 7 Twp. 16 Rge. (E) (W) 20

County Rush Total Depth 4226

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 1:15P Day 24 Month 5 Year 1970

The above well was plugged as follows:

RTD 4226' 8 5/8 csg set at 228' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 5/25/70

INV. NO. 1937-4