


15-125-20675-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202
NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 21 Twp. 18S Rge. (E) 23 (W)
Location as "NE/CNWXSWX" or footage from lines SE NW
Lease Owner Thunderbird Drilling, Inc.
Lease Name Dietz "A" Well No. 1
Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 21 1972
Application for plugging filed September 21 1972
Application for plugging approved September 21 1972
Plugging commenced September 21 1972
Plugging completed September 21 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4374 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	350.74'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 550' with 50 sacks of regular cement; plugged at 300' with 25 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 4:30 A. M. September 21, 1972.

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1972

CONSERVATION DIVISION
Wichita, Kansas

09-26-1972


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Charles W. Steincamp (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530 (Address)



Subscribed and sworn to before me this 21st day of September, 1972

My commission expires December 14, 1973

Elaine H. Taylor
Notary Public.

15135-20675-00-00

DRILLERS LOG

#1 Dietz "A"

CASING RECORD:
344.74' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.

DESCRIPTION: SE NW
Section 21-18S-23W
Ness County, Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH:
4374'

COMMENCED: September 11, 1972

ELEVATION: 2270' KB

COMPLETED: September 21, 1972

D. & A.

FORMATIONFROMTOREMARKS

Surface Soil & Rock

0

40

Shale

40

975

Dakota Sand

975

1290

Red Bed

1290

1530

Anhydrite

1530

1564

Shale & Shells

1564

2360

Lime & Shale

2360

3825

Lime

3825

4280

Sand

4280

4310

Limestone Chert

4310

4374

ROTARY TOTAL DEPTH: 4374'

Ran 344.74' of used 8-5/8" surface casing; set and cemented at 350.74' with 175 sacks of common cement, 2% gel and 3% C. G. Plug down at 10:10 P. M. September 12, 1972.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1972
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

09-26-1972

Plugged hole as follows: Plugged at 550' with 50 sacks of regular cement; plugged at 300' with 25 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 4:30 A. M. September 21, 1972.

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 21st day of September, 1972.

Elaine H. Taylor
Elaine H. Taylor, Notary Public