


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 16 Twp. 20S Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW SW SW

Lease Owner K.R.M. Petroleum Corporation
Lease Name S. G. Beltz Well No. 1
Office Address 820 Guaranty Bank Bldg., Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed 10/12 1978
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4500'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	616'	8-5/8"	16 its.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set. 60 sx. @ 660', 25 sx. @ 300', 10 sx. @ 40', 5 sx.
in rathole

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.

STATE OF Colorado COUNTY OF Denver, ss.
J. C. Simmons (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) K.R.M. PETROLEUM CORPORATION
820 Guaranty Bank Bldg., Denver, CO 80202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1978

My commission expires 1/22/79

Shirley M. Wegner
Notary Public.
Shirley M. Wegner



15-135-214750000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

S. G. Beltz #1
SW-SW-SW Sec 16-20S-21W
Ness County Kansas

Commenced: 9-30-78

Completed: 10-12-78

OPERATOR: KRM PETROLEUM CORP.

Depth		Formation	Remarks
From	To		
0	617	Sand-Shale-Shells	Ran 16 jts of 20# 8 5/8" csg
617	1210	Shale-Shells-Redbed	set @ 616' Cemented w/
1210	1457	Shale-Shells	250 sks 60/40 Posmix 2% Gel
1457	1491	Anhy	3% CC - 150 sks Common
1491	2390	Shale-Shells	2% Gel-3% CC
2390	4155	Lime-Shale	PD @ 5:30 a.m. 10-1-78
4155	4425	Lime	
4425	4500	Lime-Chert	
	4500 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 16th day of October, 1978.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

