


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Ness County, Sec. 13 Twp. 20 Rge. 21 (E)W (W)

Location as "NE/CNW%SW%" or footage from lines C SW NE

Lease Owner Pickrell Drlg. Co.; Wichita, Kans. 67202

Lease Name Isern Well No. A #1

Office Address 705 4th National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 10 19 68

Application for plugging filed April 20 19 70

Application for plugging approved April 20 19 70

Plugging commenced June 12 19 70

Plugging completed June 17 19 70

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 25 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Mississippian Depth to top 4355 Bottom -- Total Depth of Well 4377 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	270	NONE
				5 1/2	4369	2470

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

June 12, 1970 Plugged off bottom. Dumped sand to 4300'. Mixed and dumped 5 sx of cement to 4260'.

June 17, 1970 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing: 20 sx gel and 3 sx hulls Released plug and mixed and pumped 130 sx of cement + 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC
Address P.O. Box 1082 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Dale M. Robinson

705 Fourth National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 2nd day of July, 1970

Jan. 19, 1973

Esther Lamone
Notary Public.



B-135-2045-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 5/10/68
Rotary Drilling Completed 5/19/68

LOCATION: Isern "A" No. 1, C SW NE Section 13-20S-21W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 270' of 8 5/8" surface casing set with 160 sacks cement. Circulated. (145 jts) 5 1/2" casing set at 4369' with 160 sacks cement. Completed 4:30 P.M. May 10, 1968. Plugged 3:20 P.M. May 19, 1968.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Clay, Post Rock	<u>C. F. S.</u>
270	Shale, Shells & Cement	4360
620	Shale	4369
855	Red bed	4377
1060	Sand	
1421	Shale	
1457	Anhydrite	
2225	Shale	<u>Slope Test</u>
3107	Shale & Lime	2000
3620	Shale	2500
3840	Lime & Shale	3000
4166	Lime	3500
4286	Lime & Shale	4000
4304	Ft. Scott	
4340	Shale, Sand & Lime	
4351	Shale	<u>S. L. M.</u>
4377	Mississippian - RTD	
	Board	3106.19
	Strap	3105.59
	Board +	.60

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 23rd day of May, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
L. M. Whiting, Notary Public