


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Ness County. Sec. 13 Twp. 20S Rge. 21W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
150' S-SE NW NE

Lease Owner Parrish Oil Company
Lease Name Isern Well No. 2 (Twin)
Office Address 110 N. Market - Suite 201, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole

Date Well completed March 16, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced March 16, 1980
Plugging completed March 16, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 14,380'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy rotary mud from 4,380 ft. (rotary total depth) to
750 ft. Set plug at 750 ft. and cemented with 70 sacks cement. Filled
hole with heavy rotary mud from 750 ft. to 300 ft. Set plug at 300 ft.
and cemented with 20 sacks cement. Filled hole with heavy rotary mud
from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar
with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing
pump truck through 4 1/2 inch drill pipe.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982



KANSAS DRILLERS LOG

COMPANY Parrish Oil Company
 FARM Iseern NO. 2 (Twin)

SEC. 13 T. 20S -21W
 LOC. 150' S-SE NW NE

COUNTY Ness

ROTARY TOTAL DEPTH 4,380'
 COMM. March 9, 1980 COMP. March 16, 1980
 CONTRACTOR H-30, INC. (Rig #2)
 ISSUED March 27, 1980

CASING

10 3/4"
 8 5/8" Set at 306' cemented w/200 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 2,207' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Shells	308'
Sand	336'
Sand and Shale	1,403'
Anhydrite	1,448'
Shale	2,125'
Shale and Lime	2,150'
Lime and Shale	3,725'
Shale and Lime	4,010'
Lime and Shale	4,155'
Lime	4,380'
Rotary Total Depth	4,380'

I hereby certify the above and foregoing to be
 a true and correct log of the above described
 well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public
 in and for said county and state this 27th day of
 March, 1980.

Elsie Willison

 Elsie Willison - Notary Public



My Commission Expires:
 July 25, 1982

