


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 7 Twp. 20S Rge. (E) 21(W)  
Location as "NE/CNW%SW%" or footage from lines C SW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Moore Well No. 3  
Office Address 705 4th National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 22, 1964  
Application for plugging filed April 22, 1964  
Application for plugging approved April 22, 1964  
Plugging commenced April 22, 1964  
Plugging completed April 22, 1964  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4379 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with  
25 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 4 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (employee of owner, lessor, owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitt  
705 4th National Bank Building, Wichita 2, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of April, 1964

Maxine Blackman  
Maxine Blackman Notary Public.

My commission expires June 21, 1966



15-135-00304-0000  
**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 4-13-64

Rotary Drilling Completed 4-22-64

LOCATION: Moore No. 3, C SW NE Section 7-20-21W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 261', cemented with 165 sacks cement. Circulated. Completed 10:30 P.M. April 13, 1964. No oil string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Post Rock & Clay	<u>C. F. S.</u>
590	Shale & Shells	4250
770	Red Beds	4302
785	Blaine	4355
875	Red Beds, Shale & Shells	4366
1095	Sand	4370
1290	Shale & Shells	4374
1420	Shale, Shells & Red Bed	4379
1455	Anhydrite	
2110	Shale & Shells	
2530	Lime & Shale	<u>Slope Tests</u>
2730	Lime	2500
2745	Lime & Shale	3000
2820	Lime	3500
3720	Lime & Shale	4000
4315	Ft. Scott Lime	
4360	Lime	
4370	Conglomerate	<u>S. L. M.</u>
4375	Mississippi Chert	3665
4379	Mississippi - TD	3992
		4279

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 4 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebits*  
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 29th day of April, 19 64, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

*Maxine Blackman*  
Maxine Blackman Notary Public