


STATE OF KANSAS  
CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NESS County. Sec. 28 Twp. 20s Rge. 21W (X) (W)  
Location as "NE/CNW%SW%" or footage from lines C SW NE  
Lease Owner PETROLEUM, INC.  
Lease Name BELTZ Well No. 1  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 12-3- 1962  
Application for plugging filed 12-3- 19 62  
Application for plugging approved 12-3- 19 62  
Plugging commenced 12-3- 19 62  
Plugging completed 12-3- 19 62  
Reason for abandonment of well or producing formation NO OIL OR GAS FOUND  
IN COMMERCIAL QUANTITIES  
If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, HAYS, KANSAS  
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4490 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	335'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 550' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDED UP WITH HEAVY MUD TO 180' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDED UP WITH HEAVY MUD TO 40' FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor RAINS & WILLIAMSON OIL CO.  
Address 412 UNION CENTER, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) DON SEARLE, DIST. PROD. SUPT.  
ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of DECEMBER, 19 62

My commission expires APRIL 14, 1963

Arthur J. Miles  
Notary Public.



## ROTARY DRILLING LOG

Operator: Petroleum Inc.  
 NO. 1 BELTZ  
 C SW NE Sec. 23-208-21W  
 Ness County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.  
 COMMENCED: 11-20-62  
 COMPLETED: 12-3 -62

Remarks: Set 8-5/8" surface casing  
 at 335' with 165 sacks  
 common cement, 2% Jel,  
 2% Ca.Cl.

## Formations:

Surface Clay	20'
Shale	110'
Shale and Shells	195'
Sand	315'
Shale	600'
Red Bed	670'
Red Bed and Shale	900'
Sand and Shale	1120'
Shale and Red Bed	1428'
Anhydrite	1481'
Shale	1490'
Shale and Shells	2304'
Lime and Shale	2320'
Lime	2840'
Lime and Shale	3125'
Shale and Lime	3845'
Lime and Shale	3933'
Lime w/Shale Streaks	3960'
Lime	4455'
Chert and Lime	4490'
Rotary Total Depth (D & A)	4490'

We certify the above log is true and  
 correct to the best of our knowledge  
 and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains  
 Partner

Subscribed and sworn to before me, a Notary  
 Public in and for the State of Kansas,  
 County of Sedgewick, this 6th day of December,  
 1962.

*Sandra Ames*  
 Sandra Ames  
 Commission Expires August 14, 1966

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION  
 Wichita, Kansas