


K-135-19147-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 2 Twp. 20S Rge. (E) 21(W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Mauth "C" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 14, 1965
Application for plugging filed October 14, 1965
Application for plugging approved October 14, 1965
Plugging commenced October 14, 1965
Plugging completed October 14, 1965
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	468'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 460', set plug with 20 sacks cement.
Heavy mud to 240', set second plug with 10 sacks
cement. Heavy mud to 40', set plug, cemented with
10 sacks cement to bottom of cellar. Plugged rat
hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebitts
705 4th National Bank Building, Wichita 2, Ks.
(Address)

Subscribed and sworn to before me this 18th day of October, 19 65
Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966



15-135-19147-0000
ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY Rotary Drilling Commenced 10-4-65
705 4th National Bank Bldg.
Wichita, Kansas Rotary Drilling Completed 10-13-65
LOCATION: MAUTH "C" No. 1, C SE NW Section 2-20-21W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (22 jts) 8 5/8" surface casing set at 468' cemented with 200 sacks cement. Circulated. Completed 6:00 P.M. October 4, 1965. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

140	Top Soil & Clay	<u>C. F. S.</u>
468	Shale, Sand Streaks	4425
825	Shale, shells & Red Bed	4428
837	Blaine	4450
918	Shale, Red Beds	
1127	Sand	
1490	Red Beds, Shale & Shells	<u>Slope Tests</u>
1530	Anhydrite	2500
2225	Shale & Shells	3000
2425	Shale & Lime	3500
2665	Lime	4000
3825	Shale & Lime	
3960	Lime	<u>S. L. M.</u>
4020	Lime & Shale	3797
4346	Lime	4055
4420	Lime & Shale	4318
4450	Mississippian - RTD	

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1965

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 18th day of October, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITTS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public