

15-135-19109-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 36 Twp. 17 Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Kimbark Exploration Company
Lease Name Norton Well No. 1
Office Address Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-5-65 19____
Plugging completed 5-6-65 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4408 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None
				4-1/2"	4400'	2683'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4408', sanded to 3390' and dumped 4 sacks of cement @ 3390' with dump bailer. Pulled 4 1/2" casing to 700' and circulated with 40 sacks of gel mud. Pumped in 20 sacks of cement @ 700'. Pulled casing to 200' and pumped in 20 sacks of cement. Pulled balance of casing, bailed fluid to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1965

PLUGGING COMPLETE.


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 19 65



My commission expires May 20, 1968

Milton J. Volin
Notary Public.

Kimbark Exploration # 1 Norton

Location: C SW NE Sec. 36 T17S R26W
Ness Co. Kansas

Spudded: 8/3/63
Completed: 8/21/63

Owner: Kimbark Exploration Company
201 University Blvd.
Denver 6, Colorado

Contractor: Kimbark Expl. Co.
201 University Blvd.
Denver 6, Colorado

Surface casing: 8 5/8" @ 219 w/165 Sacks of cement.

Oil String: 4 1/2" @ 4400' w/75 sacks of cement.

LOG

Figures indicate bottom of formation

- 0-221 Clay & sand
- 221-1158 Shale
- 1158-2000 Shale, shells & anhydrite
- 2000-2590 Shale & lime
- 2590-2838 Lime & shale
- 2838-3102 Lime
- 3102-3345 Lime
- 3345-3504 Lime
- 3504-3732 Lime
- 3732-3840 Lime & shale
- 3840-3969 Lime & shale
- 3969-4092 Lime
- 4092-4180 Lime
- 4180-4241 Lime
- 4241-4330 Lime & shale
- 4330-4403 Lime
- 4403-4410 Lime
- 4410-TD Lime

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, W. K. Arbuckle, President of Kimbark Exploration Company, hereby certifies that the above is a true and correct log of the formations encountered in drilling the # 1 Norton as shown in the daily drilling reports.

KIMBARK EXPLORATION COMPANY

W.K. Arbuckle

W.K. Arbuckle, President

STATE OF COLORADO)ss.
CITY & COUNTY OF DENVER

Be it remembered that on this 30th day of April A.D. 1965 before me, Barbara J. Dodson, a Notary Public, personally appeared W.K. Arbuckle, President of Kimbark Exploration Company, a Colorado Corporation, who is personally known to me and known to me to be the President of said Corporation, and the same person who executed the foregoing instrument, and he duly acknowledged the execution of the same, for and on behalf of and as the act and deed of said Corporation.

WITNESS my hand and official seal:
My Commission Expires January 28, 1968



Barbara J. Dodson
Notary Public